Boomtrux, Inc.

9513 Dr. MLK Blvd., Suite 1 Tampa, FL 33610 877-543-2207 Toll Free 813-247-5683 Office 813-833-2187 Cell carlton@boomtrux.com



(1) 2009 Manitex 40100S / 2009 Sterling 9513

Date: 2/25/2016 To: Manitex 40100S for Crane Network

Quote#: BTX 1054CB40
Sales Price: \$187,500.00
Sales Tax: not included
Freight: FOB Tampa
Crane SN: 157217

Truck SN: 2FZHAZCV99AAF3813

F3813	Accepted:	
-3013	ACCEDIEG.	

2009 Manitex 40100S 40 Ton

40 ton @ 5' radius with heat & AC in cab 100' 4 section, 110' tip height hydraulic boom 3 sheave boom tip / 2,250# counterweight 360 continuous rotation with "Free Swing" 2 speed planetary winch w/13,050# line pull @ 453' per minute max. line speed and hoist drum rotation indicator 380' of 5/8" rotation resistant wire rope. ACUSswing sets rotation speed up to 2 RPM Out/down 22' full span, 13'4" mid-range & 7'2" retracted spread outriggers w/alarms Universal front bumper outrigger installed **CANbus LMI System. Operator access to all** load configurations at display. Radio A2B system with internal boom length cable Single axis pilot controls includes throttle, engine stop, horn, LMI display, angle indicator, load chart & range diagram 100 gallon hydraulic tank with (2) 25 micron filters and hydraulic oil cooler State of the Art automotive electrical system 3 section hydraulic pump (41.7/28/12 GPM) SAE Face Seal O-Ring fittings in entire system 30-55' 2 stage jib included / block/ball

2009 Sterling 9513 Chassis

113" BBC 70.000# GVW Chassis MBE 4000 410HP Diesel (1,450 ft./lb.) Allison 4500 series automatic transmission Horizontal muffler with vertical exhaust 20,000# capacity Meritor Front Axle 40,000# capacity Meritor Rear Axles 4:33 rear ratio with axle/diff lock outs Bendix ABS air brake system HD 30.0 section modulus frame 70 gallon aluminum fuel tank Steel disc wheels on front and rear 425/65R 20 ply flotation front tires 11.22.5 14 ply rear tires AC/Heater, gauge package, air driver seat, fixed passenger seat, AM/FM, Cruise Control, painted grille and bumper 26,597 miles as of 1/6/2016 2.787 hours as of 1/6/2016 48" steel tool box installed 12.000# lift axle installed